AQUA PURE PACKAGED DRINKING WATER

CENTRAL QUALITY ASSURANCE & TESTING LABORATORY | NABL ACCREDITED & BIS IS 14543

Industrial Area Phase II, SIPCOT Complex | FSSAI Central License No. 10018042000000

20L Commercial Can Batch Quality Analysis Certificate

Comprehensive Chemical Assay, 7-Stage Can Sanitization & Ozone Residue Verification

Certificate No: AP/QA/AQ-2026-CAN-20L-338 | Sampling Date: 04-Nov-2026 | Testing Completed: 05-Nov-2026

Batch / Lot: AQ-2026-CAN-20L-108 | Sample Format: 20L Polycarbonate Multi-Trip Can | Status: PASS / CONFORMS

Testing Protocol: IS 3025 / IS 14543 | Sampling Location: Automated Filler Line-B | Release Authorization: Dr. S. Rao, Chief Chemist

Parameter Evaluated	Test Method	Observed Value	BIS IS 14543:2018 Limit	Status
pH Value (at 25 deg C)	IS 3025 (Part 11)	**7.22**	6.5 - 8.5	**PASS**
Total Dissolved Solids (TDS)	IS 3025 (Part 16)	**98.5 mg/L**	75 - 150 mg/L	**PASS**
Turbidity	IS 3025 (Part 10)	**0.06 NTU**	Max 2.0 NTU	**PASS**
Total Hardness (as CaCO3)	IS 3025 (Part 21)	**54.2 mg/L**	Max 200 mg/L	**PASS**
Calcium (as Ca)	IS 3025 (Part 40)	**18.4 mg/L**	Max 75 mg/L	**PASS**
Magnesium (as Mg)	IS 3025 (Part 46)	**8.2 mg/L**	Max 30 mg/L	**PASS**
Chlorides (as Cl)	IS 3025 (Part 32)	**22.8 mg/L**	Max 200 mg/L	**PASS**
Sulphates (as SO4)	IS 3025 (Part 24)	**11.5 mg/L**	Max 200 mg/L	**PASS**
Residual Ozone Concentration	DPD Colorimetric	**0.14 mg/L**	0.10 - 0.20 mg/L	**PASS**
Aerobic Microbial Count	IS 5402 (37 deg C)	**0 CFU/ml**	Max 20 CFU/ml	**PASS**
Total Coliform Bacteria	IS 5401	**Absent / 250ml**	Absent in 250ml	**PASS**
Internal Wash Alkaline Residue	Acid-Base Titration	**Nil (<0.001 ppm)**	Undetectable	**PASS**

STATUTORY LABORATORY CONCLUSION & DISPATCH CLEARANCE:

This batch sample conforms in all measured physical, chemical, and microbiological parameters to IS 14543:2018 specifications. The production batch is certified safe, sterile, and formally released for consumer distribution.

T. N. Sharma, M.Sc.
Senior Analytical Chemist

Dr. S. Rao, Ph.D.
Chief Quality Controller

Er. M. Venkatesh
Plant Operations Director